

Pine Mountain Estates FEMA Project

Sewer Treatment Area

Scope of work (all materials and labor included)

- Reconstruction and dredging/rerouting of creek and embankment at sewer treatment area, including rock rip-rap shoreline (approximately 15-20' width x 850' length)
- Replace chain link fence at left side perimeter of sewer treatment area to connect to existing fence (approximately 600' in length)
- Demo existing bridges and rebuild at sewer treatment area

Bridge Work

Scope of work (all materials and labor included)

- Bridge #1 (Steel)
Raise, level, and install new footer and paint upon completion
- Bridge #2 (Far side trailer bed bridge)
Remove existing steel rail columns
Install decking with rough cut 2x6 material
Install 6x6 outer curb
- Bridge #3 (Pole construction)
Remove existing deck boards and realign pole supports
Install decking with rough cut 2x6 material
Install 6x6 outer curb

The above work to be performed in accordance with the specifications submitted for the above work completed in a substantial manner for the sum of **\$230,000** to be paid in the following installments: 50% (\$115,000) at signing of contract, 20% (\$46,000) at completion of creek work, 20% (\$46,000) at completion of remaining Sewer Treatment Area work, 10% (\$23,000) at completion of Bridge Work.

Acceptance of Proposal

The above price, specifications, and conditions hereby accepted. A & D Painting and Contracting is authorized to do the work specified. Payment will be made as outlined above.

Signature _____

Date _____

Print Name _____